

11. The time limit specified in para 10 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his five per cent deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly.

12. Plans and specifications and other details of work to be done or available for inspection in the Senior Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

13. In all matters of dispute regarding rates, measurement, quality of work, etc.; and in all disputes of any kind, the decision of the Superintendent, Way and Works, Mysore Railways, Mysore, will be final and legally binding.

14. Contractors should make their own arrangements for water required for the work and Departmental water will not be supplied.

Schedule.

Sl. No.	Particulars	Per	Quantity
1	Constructing compound wall as per design of the existing compound wall and as per specification.	R.ft.	720
2	Dismantling existing compound wall and rebuilding using new bricks in addition to released bricks (bricks less than 5" in length should not be used).	"	560

Specifications.

Foundations.—Concrete broken stone in sand mortar one ft. deep and one foot nine inches wide.

Over concrete, burnt brick in mortar masonry one foot six inches wide and six inches high.

Basement.—Burnt brick in mortar masonry one foot six inches wide and one foot high.

Superstructure.—Burnt brick in prepared mud one foot one and a half inches wide and eight feet high above basement excluding coping.

Coping.—Burnt brick in mortar one foot high; one and a half foot wide at the base. Coping to be plastered in cement mortar and glass pieces should be fixed over it in cement mortar as close as possible.

Pillasters are to be at 15 feet centres two feet three inches square. The thickness of pillasters at foundation and basement including concrete to be made suitably thicker as shown in the plan. The whole wall both sides inclusive of foundation above concrete should be plastered with chunam mortar and white washed as shown in the plan.

Materials, and their proportions, and method of building should conform to Marryat's Hand Book, Volume I.

R. N. MIRZA,
Senior Executive Engineer.

MISCELLANEOUS DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER, BANGALORE.

Abstract dated 19--20th July 1933.

Attention of the public is invited to the two detailed Notifications relating to tenders for the supply of the following, published on pages 936-941 of Part VI of the *Mysore Gazette* dated 27th July 1933 :—

1. Printing and Supplying Books, Forms, etc.
2. Supplying Stationery.

The tenders are due in the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, on or before the 10th August 1933 at 12 noon with a deposit of Rs. 100 for item No. 1 only.

V. R. COWSIK,
For Chief Electrical
Engineer.